

**NORTH DELHI MUNICIPAL CORPORATION**  
**OFFICE OF THE EXECUTIVE ENGINEER (PROJECT) -I/ ROHINI**  
**SUB-ZONAL OFFICE BUILDING**  
**2ND FLOOR, SECTOR -17, ROHINI : DELHI**

No. EE (Pr.)-I/Rohini/2015-16/ 898

Dated: 10/12/15


**CORRIGENDUM**

In NIT no. EE(Pr.)-I/Rohini/TC/2015-16/09 dated 04.12.2015, the quantity for item no. 16 (b) has not been indicated. The quantities for item no. 16 (a) and 16 (b) are as under:

| Item no. | Description of item  | Quantity | Unit | Quoted Rate (Rs.) | Amount (Rs.) |
|----------|--|----------|------|-------------------|--------------|
| 16       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work upto plinth level:<br>a) 1.1.5:3 (1 Cement 1.5 coarse sand and :3 graded stone aggregate 20mm nominal size) | 30.24    | cum  |                   |              |
|          | b) 1:5:10 ( 1 Cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size)   | 6.04     | cum  |                   |              |

The item no. 17 i.e. 'Providing and fixing rubber flooring 25 mm thick made of SBR (Styrene Butadiene Rubber) with interlocking arrangement and adhesive all complete colour and size as approved by Engineer-in-Charge' stands deleted.

All other terms & conditions of the NIT will remain same.

  
10.12-15

**Ex. Engineer (Pr.)-I/Rohini**

Executive Engineer (Pr.) Rohini  
Sub Zonal Office  
2nd Floor, Sector-17,  
Rohini, Delhi

All concerned