

<b>Name Of Work : Construction, Operation and Maintenance of Automated Multilevel Car Parking facility at J Block Market, Rajouri Garden, West Zone, Delhi -110027</b>						
<b>CORRIGENDUM</b>						
<b>S. NO.</b>	<b>DSR item No 2016</b>	<b>DESCRIPTION</b>	<b>UNIT</b>	<b>QTY</b>	<b>RATE</b>	<b>AMOUNT(RS)</b>
<b>BILL OF QUANTITIES FOR CIVIL WORKS</b>						
2.6	5.22	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level.				
2.6.1	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more. <b>(Earlier)</b>	KG	#####	----	----
2.6.1	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more <b>(Revised)</b> .	KG	199978.28		
2.7	5.22A	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete above plinth level.				
2.7.1	5.22.A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more <b>(Earlier)</b> .	KG	#####	----	----
2.7.1	5.22.A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more. <b>(Revised)</b>	KG	149038.19		
5.1	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. <b>(Earlier)</b>	KG	#####	----	----
5.1	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. <b>(Revised)</b>	KG	399172.50		
<b>BILL OF QUANTITIES FOR PLUMBING WORKS</b>						
1.6		Providing and fixing multi-jet magnetic drive (turbine type) water Meter conforming to IS:779 with direct reading dia in Kilo-liter with all internal part in Gun metal or brass, strainer, flanged distance pieces for easy removal, 100 mm dia burden type pressure gauge with isolation cock including necessary test certificates for the Meter from municipal authority.				
		25/32/40/50 mm dia <b>(Earlier)</b>	Each	1	----	----

S. NO.	DSR item No 2016	DESCRIPTION	UNIT	QTY	RATE	AMOUNT(RS)
1.6		Providing and fixing multi-jet magnetic drive (turbine type) water Meter conforming to IS:779 with direct reading dia in Kilo-liter with all internal part in Gun metal or brass, strainer, flanged distance pieces for easy removal, 100 mm dia burden type pressure gauge with isolation cock including necessary test certificates for the Meter from municipal authority.				
		25mm dia <b>(Revised)</b>	Each	1		
<b>BILL OF QUANTITIES FOR ELECTRICAL WORKS</b>						
<b>PART II</b>						
1 (i)		Supply of 1 x 20 watt surface/wall mounting type LED tube light with fitting and complete with all accessories : <b>(Earlier)</b>	Each	450	----	----
1 (i)		Supply of 1 x 18 watt surface/wall mounting type LED tube light with fitting and complete with all accessories : <b>(Revised)</b>	Each	450		
<b>PART V</b>						
5.00		Supplying, Erection, Installation, Testing & commissioning of Down conductor Recommended : 70 Sqr mm insulated copper Flexible cable for lightning current dissipation to earth with necessary Fixing Clamp, Connector accessories etc. <b>(Earlier)</b>	Each	75	----	----
5.00		Supplying, Erection, Installation, Testing & commissioning of Down conductor Recommended : 70 Sqr mm insulated copper Flexible cable for lightning current dissipation to earth with necessary Fixing Clamp, Connector accessories etc. <b>(Revised)</b>	MTR	75		
<b>NOTE: IN ORDER TO CORROSPOND WITH THE ITEM DESCRIPTION IN CIVIL WORKS OF ITEM S No 6.4 , THE HEADING FOR FULL BODY VITRIFIED TILE TO BE READ AS MATT FINISH FULL BODY VITRIFIED TILE</b>						